

Projekt: **NHS**

Place: Portsmouth Latitude: 51,0°

Kollektor: **87,50 m²** ARCON HT

Linie: c0 = 0,780 c1 = 3,500 W/(m²K) c2 = 0,002 W/(m²K²)

Degrees: 45,0° from south: 0,0°

Systemtype: Warmwaterheating


Boiler: 5000 l Temperature: min. 42°C / max. 75°C

Heat Requirement: 348,90 kWh/d (6000 Liter/day from 10°C to 60°C)


month	Solar-gain [kWh]	Solar Radiation [kWh]	Conventional energy [kWh]	% of total energy requirement [%]	System efficiency [%]
Jan:	2586,9	4694,1	8278,4	23,8	55,1
Feb:	3369,1	6244,8	6825,5	33,1	54
Mar:	5251,8	9962,7	5645,3	48,2	52,7
Apr:	6044,6	11988,9	4542,6	57,2	50,4
Mai:	6527,3	13295,2	4383,2	59,8	49,1
Jun:	6856,9	14042,1	3715,6	64,9	48,8
Jul:	7174,4	14343,6	3757,7	65,7	50
Aug:	6654,6	12789,4	4247,4	61	52
Sep:	6308,6	11795,1	4238,5	59,7	53,5
Okt:	4497,7	8172,5	6389,7	41,3	55
Nov:	2630,3	4663,9	7882,8	25	56,4
Dec:	2082,4	3677,3	8468,5	19,8	56,6
total:	59984,6	115669,6	68375	46,7	51,9

yearly specific kollektor gain: **686 kWh/m²**

Solar earn and konventionell heat



Solarenergy requirement and efficiency



yearly
 spared konventionell heat: 59984,6 kWh
 price of konventionell heat: 0,05 pound / kWh
 yearly spared pounds: **2999,23** pound

Systems kosts:	peaces	total	
Kollektors	600	7	4200
mountingpeaces	100	7	700
Pipeline (m)	12	30	360
Boiler	1	3000	3000
pumpstation	1	600	600
elektronics	1	1000	1000
			0
mounting	200	15	3000
			0
surprises:	1000	5	5000
			0
			<u>17860</u>
paybacktime in years:			<u>6,0</u>

month	% of total e System requirement	
	[%]	[%]
Jan:	23,8	55,1
Feb:	33,1	54
Mar:	48,2	52,7
Apr:	57,2	50,4
Mai:	59,8	49,1
Jun:	64,9	48,8
Jul:	65,7	50
Aug:	61	52
Sep:	59,7	53,5
Okt:	41,3	55
Nov:	25	56,4
Dec:	19,8	56,6
mean:	46,7	51,9

59984,6 173955,3